


A. Project Definition

This MPMP proposes an establishment of an ITF (Integrated Treatment Facilities) in Cilincing, North Jakarta to manage the MSW (Municipal Solid Waste) in Jakarta by the second quarter of 2019. ITF is a facility to apply the 3R (Reduce, Reuse, Recycle) principle in order to minimize negative environmental impacts, such as leachate liquid and methane (greenhouse gas) from landfill. Beside of that, this new ITF will help Jakarta government overcome difficulties with Bantargebang ITF nearby citizen and manage Jakarta's MSW which is predicted to increase every year. This achieved by establishing the ITF based on the 3Rs (Reduce, Reuse, Recycle) principle.

B. Background

Nowadays, the life of people surrounding Bantargebang, Bekasi, is suffering. Bantargebang is known as one of the largest ITF in Indonesia. Historically, many landfills around the world have failed and caused human surrounding it to suffer due to the leachate and methane (greenhouse gas) produced by landfills. Greenhouse gas has been known as the cause of global warming while leachate is a hazardous liquid that contaminates soil water and pipes surrounding it. Once a landfill is built, maintenance and repair is impossible which causes leachate easily spread.



The main source of waste in Bantargebang is sent from Jakarta and is predicted to increase every year (Kompas.com, 2014). In a day, Jakarta delivers around 6500 tons to Bantargebang

although around 7200 tons is generated (Kompas.com, 2016).


These situations is analyzed in an SCQ (Situation-Condition-Question Framework) which is continued with an issue tree analysis. This results in 5 main issues which are as landfill condition, ITF capability, waste treatment in Jakarta, population and lifestyle.

By considering the sustainability development (economic, social, and environmental) impact of each issue, waste treatment in Jakarta


Situation	Complication	Question
<ul style="list-style-type: none"> Landfills produces leachate, a hazardous liquid and methane, a greenhouse gas Once a landfill is built, maintenance is not possible Leachate will contaminate soil and water once a landfill is worn out Bantargebang is one of the largest landfill in Indonesia with around 80 Ha used for waste landfill and treatment facilities The waste in Bantargebang landfill reaches 25 meters high 	<ul style="list-style-type: none"> Bantargebang produces fertilizer from organic waste and energy by utilizing methane The citizen near Bantargebang is suffering due to water contamination near the site Bantargebang accepts around 6500 tons of solid waste from Jakarta everyday Jakarta generates around 7000 tons of waste/day The waste generated in Jakarta has an increasing trend every 5 years 	<ol style="list-style-type: none"> Bantargebang has caused near citizen suffer due to the landfill's hazard The biggest source of waste in Bantargebang is from Jakarta In average, there is 600 tons of waste remains in Jakarta
<ol style="list-style-type: none"> How to manage waste in Jakarta and reduce suffering of Bantargebang citizens ? 		

SCQ - Framework

is place as first priority to overcome. The landfill in Bantargebang is unrepairable, improving Bantargebang ITF capacity needs landfill relocation and it is not feasible, population in Jakarta follows an increasing trend every year, lifestyle change will not give significant impact, while scheduling in Bantargebang will be affected by the waste treatment in Jakarta.



Better waste treatment in Jakarta means that better methods are needed. One of the better methods for Jakarta is by establishing a new ITF. In accordance with the Jakarta Development Plan for 2030 (see [Appendix A](#)), one possible place for ITF establishment is in Cilincing, North Jakarta.



Initial (Left) and Expected (Right) Distribution Map of Waste

With a new ITF in Cilincing, hopefully Jakarta can be cleaner and diminish the social burden of Jakarta in Bantargebang. Beside of that, the distribution cost may reduce, support farmers with cheaper fertilizer produced by the ITF, society can maximize reuse of recyclables, etc.

C. Project Objective

The main objective of this project is to minimize waste in DKI Jakarta, distribution cost of waste, environmental impact of landfills, and prosper the society of DKI Jakarta and Bekasi with the establishment of ITF in Cilincing. This ITF is planned to be finished on April 15th, 2019 with the support of the DKI Jakarta Government. The success of this project will be measured by reduced waste left in DKI Jakarta with lower distribution cost and processing cost than the initial condition and also reduce of landfills usage for DKI Jakarta especially in Bantargebang landfill. The project

will begin on August 2nd, 2016 with the whole process estimated to finish around 3 years and cost around 2.9 trillion Rupiahs.

D. Scope Statement

The project scope description of this project will be operating facility for Integrated Municipal Solid Waste Treatment with area of 16 Ha. The MSW processed by the company varies and also will end up various product which includes organic waste treated to be fertilizer; combustibles into energy source; recyclable will be bailed up to be sold and reused by demanding stakeholders; and other waste will be distributed to other ITFs.

E. Acceptance Criteria

The acceptance criteria before the project deliverables can be handled are as follows:

- DKI Jakarta Government must start a 3R campaign and also minimize landfills campaign to the society
- The waste from household are be presorted and kept in original state of waste
- Waste distribution schedule in DKI Jakarta has been established

F. Deliverables

Listed below are the major deliverables of this project.

1. Construction Planning
2. Construction
3. Legal and Regulatory
4. Testing
5. Reporting and Documentation

G. Project Exclusion

The exclusions of this project are as follows:

- Post facility establishment human resource procurement
- Post facility establishment maintenance and development plan

H. Constraints

Listed below are the constraints of this project is based on 6 constraints category which includes schedule, quality, budget, resources, risk, and scope.

Schedule Constraints

- Standard working time is 8 hours a day from 08:00 up to 12:00 and 13:00 up to 17:00
- Work will be done 5 days a week from Monday to Friday while Saturday and Sunday are nonworking days
- The project must finish before April 15th, 2019

Quality Constraints

- During project all activities must follow the national HSE (Health, Safety, and Environmental) regulations
- The ITF must fulfill ISO 14001 about Environmental Management
- All of the ITF components must fulfill SNI (Indonesia National Standard)

Budget Constraints

- Maximum budget usage is IDR 3,000,000,000,000.-

Resources Constraint

- Construction phase is done by 3rd party which makes the construction resources included in the corresponding work agreement/pack
- All of the resource are always available during the project

Risk Constraint

- The exchange rate for US\$ 1 is initially set to be IDR 14,000.- , but with probability 0.2 to fluctuate

Scope Constraints

- The land allocation is 25 ha and at most 16 ha for building
- 8 ha land left is allocated for greenery and further development
- 16 ha of ITF is able to process 10000 tons of MSW/day


I. Assumptions

The assumptions in this project are as follows:

- The budgeting of this project is given by the Government of DKI Jakarta, Sanitary Department of DKI Jakarta, and other investors
- Feasibility study indicates that the project is feasible.
- Governance change will not affect the project plan

J. Work Breakdown Structure


Below is the Work Breakdown Structure (WBS) of ITF Establishment in Cilincing. This WBS is built based on the decomposition of deliverables.



Work Breakdown Structure of ITF Establishment in Cilincing


K. Project Time

This project is planned to start on August 2nd, 2016 with duration 537 days to finish on August 28th, 2018 before adding contingency reserve. This is obtained by analyzing the project deliverables dependencies and duration by drawing the precedence diagram of this project. The precedence diagram is available in the figure below.




ITF Establishment in Cilincing Precedence Diagram

The image below presents the bar chart for the activities schedule of this project. This schedule is developed based on the precedence diagram above.



Project Activities Schedule Bar Chart (Larger Image in [Appendix B](#))

Each activity in a project must always end up with specific signs. In order to present specific signs of each activities, a list of milestones is developed. Below is the list of milestones along with each milestone's tentative date.



Project Milestones List and Chart (Larger Image in [Appendix C](#))

L. Master Budget


Listed below is the Project Budget Base (PBB) of this project.

WBS	Task Name	Cost	Duration	Start	Finish	Project Expenses (Million IDR)																							
						2016												2017											
Project Budget Base		2,992,000,000.00																											
Management Reserve		272,000,000.00																											
Performance Measurement Baseline (PMB)																													
1	ITF Establishment in Cilincing	2,151,909,564.000	538	Mon 08/08/16	Wed 29/08/18	133.18	169.76	300,054.47	1,450,389.05	198,003.04	200.07	216.58	277.32	244.48	277.35	200.09	248.82	277.32	248.82	200.07	200.85	248.82							
1.1	Construction Planning	26,809,599	8	Mon 01/09/16	Mon 12/09/16	26.81																							
1.2	Construction	169,737,816.687	432	Tue 06/12/16	Wed 01/04/17							75.73	78.99	71.81	82.35	79.31	82.35	78.99	75.43	82.35	75.43	78.58	79.39	75.43					
1.2.1	Site Development	227,723,996	85	Tue 06/12/16	Mon 03/04/17							58.79	56.99	51.81	58.80	52.35													
1.2.2	Civil Structures	712,207,986	272	Tue 04/04/17	Wed 18/04/18																								
1.2.3	Electrical Systems	26,489,999	10	Thu 19/04/18	Wed 02/05/18												56.79	59.80	56.99	54.40	59.80	54.40	56.98	55.80	54.40				
1.2.4	Thermal Systems	202,243,996	15	Thu 03/05/18	Wed 23/05/18																								
1.2.5	Storage Systems	1,876,643,963	5	Thu 19/04/18	Wed 25/04/18																								
1.2.6	Mechanical Systems	156,202,672,951	20	Thu 24/05/18	Wed 20/06/18																								
1.2.7	Instrumentation and Control Systems	159,697,997	30	Thu 21/06/18	Wed 01/08/18																								
1.2.8	Auxiliary Systems	893,409,983	7	Thu 03/05/18	Fri 11/05/18																								
1.2.9	Security System	51,449,999	7	Thu 19/04/18	Fri 27/04/18																								
1.2.10	Flow Systems	7,657,817,851	20	Mon 09/04/18	Fri 04/05/18																								
1.2.11	Environmental Systems	692,761,986	25	Thu 15/03/18	Wed 18/04/18																								
1.3	Legal and Regulatory	1,977,850,857,397	86	Mon 08/08/16	Mon 05/12/16	16.21		320.03.02	1,403,168.54	197,700.00																			
1.3.1	Licensing		59	Tue 13/09/16	Fri 02/12/16																								
1.3.2	Government Permitting and Agreement		30	Tue 13/09/16	Mon 24/10/16																								
1.3.3	Land Acquisition	1,977,834,645,398	30	Tue 25/10/16	Mon 05/12/16			129.03.02	1,403,168.54	197,700.00																			
1.3.4	Sustainability Impact Assessment	16,212,000	18	Mon 08/08/16	Wed 31/08/16	16.21																							
1.3.5	Contractor Agreements		18	Tue 25/10/16	Thu 17/11/16																								
1.3.6	Work Agreements		12	Fri 18/11/16	Mon 05/12/16																								
1.3.7	Other Legal/Regulatory Requirements		6	Mon 28/11/16	Mon 05/12/16																								
1.4	Testing	2,100,000	6	Thu 02/08/18	Thu 09/08/18																								
1.5	Reporting and Documentation	795,983,984	452	Tue 06/12/16	Wed 29/08/18							39.96	38.74	35.21	40.40	35.21	40.40	38.74	36.96	40.40	36.96	38.73	38.76	36.96					
1.5.1	Annual Project Report	4,298,000	433	Tue 06/12/16	Thu 02/08/18							0.11	0.21	0.21	0.24	0.11	0.21	0.24	0.21	0.24	0.21	0.21	0.21	0.24	0.11				
1.5.1.1	Project Documentation	2,436,000	433	Tue 06/12/16	Thu 02/08/18							0.11	0.11	0.11	0.14	0.11	0.14	0.11	0.14	0.11	0.14	0.11	0.11	0.14	0.11				
1.5.1.2	Report Writing	532,000	394	Wed 04/01/17	Mon 09/07/18							0.03	0.03	0.03	0.03	0.03	0.03	0.03	0.03	0.03	0.03	0.03	0.03	0.03	0.03				
1.5.1.3	Report Publishing	1,330,000	392	Mon 09/01/17	Tue 10/07/18							0.07	0.07	0.07	0.07	0.07	0.07	0.07	0.07	0.07	0.07	0.07	0.07	0.07	0.07				
1.5.2	Final Project Report	686,000	14	Fri 10/08/18	Wed 29/08/18																								
1.5.2.1	Report Writing	406,000	12	Fri 10/08/18	Mon 27/08/18																								
1.5.2.2	Report Publishing	280,000	2	Tue 28/08/18	Wed 29/08/18																								
Contingency Reserve		568,090,436.000	163	Thu 30/08/18	Mon 15/04/19																								

WBS	Task Name	Cost	Duration	Start	Finish	Project Expenses (Million IDR)																							
						2018												2019											
1	ITF Establishment in Cilincing	2,151,909,564.000	538	Mon 08/08/16	Wed 29/08/18																								
1.1	Construction Planning	26,809,599	8	Mon 01/09/16	Mon 12/09/16	272.58	296.58	597.97	8,669.47	49,726.84	109,512.27	164.02	782.88																
1.2	Construction	169,737,816.687	432	Tue 06/12/16	Wed 01/04/17	82.59	71.81	415.87	8,496.04	49,536.85	109,378.85	132.36	606.86																
1.2.1	Site Development	227,723,996	85	Tue 06/12/16	Mon 03/04/17																								
1.2.2	Civil Structures	712,207,986	272	Tue 04/04/17	Wed 18/04/18	59.60	51.81	56.99	33.68																				
1.2.3	Electrical Systems	26,489,999	10	Thu 19/04/18	Wed 02/05/18				24.79	3.70																			
1.2.4	Thermal Systems	202,243,996	15	Thu 03/05/18	Wed 23/05/18					202.24																			
1.2.5	Storage Systems	1,876,643,963	5	Thu 19/04/18	Wed 25/04/18						1,876.64																		
1.2.6	Mechanical Systems	156,202,672,951	20	Thu 24/05/18	Wed 20/06/18																								
1.2.7	Instrumentation and Control Systems	159,697,997	30	Thu 21/06/18	Wed 01/08/18						46,889.54	109,313.54	44.32	110.36	5.93														
1.2.8	Auxiliary Systems	893,409,983	7	Thu 03/05/18	Fri 11/05/18																								
1.2.9	Security System	51,449,999	7	Thu 19/04/18	Fri 27/04/18																								
1.2.10	Flow Systems	7,657,817,851	20	Mon 09/04/18	Fri 04/05/18																								
1.2.11	Environmental Systems	692,761,986	25	Thu 15/03/18	Wed 18/04/18				336.69	356.08																			
1.3	Legal and Regulatory	1,977,850,857,397	86	Mon 08/08/16	Mon 05/12/16																								
1.3.1	Licensing		59	Tue 13/09/16	Fri 02/12/16																								
1.3.2	Government Permitting and Agreement		30	Tue 13/09/16	Mon 24/10/16																								
1.3.3	Land Acquisition	1,977,834,645,398	30	Tue 25/10/16	Mon 05/12/16																								
1.3.4	Sustainability Impact Assessment	16,212,000	18	Mon 08/08/16	Wed 31/08/16																								
1.3.5	Contractor Agreements		18	Tue 25/10/16	Thu 17/11/16																								
1.3.6	Work Agreements		12	Fri 18/11/16	Mon 05/12/16																								
1.3.7	Other Legal/Regulatory Requirements		6	Mon 28/11/16	Mon 05/12/16																								
1.4	Testing	2,100,000	6	Thu 02/08/18	Thu 09/08/18																								
1.5	Reporting and Documentation	795,983,984	452	Tue 06/12/16	Wed 29/08/18	40.46	35.21	38.74	36.96	40.40	36.96	38.71	37.46																
1.5.1	Annual Project Report	4,298,000	433	Tue 06/12/16	Wed 02/08/18	0.21	0.21	0.24	0.21	0.24	0.21	0.21	0.03																
1.5.1.1	Project Documentation	2,436,000	433	Tue 06/12/16	Thu 02/08/18	0.11	0.11	0.14	0.11	0.14	0.11	0.11	0.03																
1.5.1.2	Report Writing	532,000	394	Wed 04/01/17	Mon 09/07/18	0.03	0.03	0.03	0.03	0.03	0.03	0.03	0.03																
1.5.1.3	Report Publishing	1,330,000	392	Mon 09/01/17	Tue 10/07/18	0.07	0.07	0.07	0.07	0.07	0.07	0.07	0.07																
1.5.2	Final Project Report	686,000	14	Fri 10/08/18	Wed 29/08/18																								
1.5.2.1	Report Writing	406,000	12	Fri 10/08/18	Mon 27/08/18																								
1.5.2.2	Report Publishing	280,000	2	Tue 28/08/18	Wed 29/08/18																								
Contingency Reserve		568,090,436.000	163	Thu 30/08/18	Mon 15/04/19																								


The PBB above is made based on several budget list which are activity, usage, and undistributed cost of this project (available in [Appendix D](#)). The PBB for this project is IDR

2,992,000,000,000. Below is the planned value chart of the project obtained from project time and budget.



M. Stakeholder Analysis

Below is the stakeholder analysis for selected stakeholders. The full list is available in [Appendix E](#). From the stakeholders analysis a stakeholder matrix is developed (available on the image in the right).



ID	Stakeholder	Description	Power (Level 1-10)	Interest (Level 1-10)	Engagement Phase	Communication Plan
B	DKI Jakarta Government	Main authority owner	Very High (10) 1. Have a right to change project plan 2. Responsible for agreement	Very High (10) 1. Project Plan 2. Project Progress and Report 3. Cleaner Jakarta 4. Project Objectives	Whole Project Phase Will be engage at the beginning of the project due to the importance of waste management, regulatory, and also given annual reports until project finish.	Interactive Communication Media: Meetings, video conference, e-mail, cloud storage, fax annual report
L	Citizen of DKI Jakarta	Society who lives in DKI Jakarta and mainly generates waste	Very Low (1) 1. Affect Political Decisions	Moderate (6) 1. Cleaner Jakarta 2. Project Progress and Report	Whole Project Phase Will be engage at the beginning until	Push Communication Media: Television, radio, newspaper,

ID	Stakeholder	Description	Power (Level 1-10)	Interest (Level 1-10)	Engagement Phase	Communication Plan
					the end of the project due to the project information transparency.	websites, annual reports
M	Main Contractors	Person responsible for the whole construction site activity	Very High (10) 1. Responsible for the whole construction phase	Very High (9) 1. Project Plan 2. Project Progress and Report 3. Project Objective	1. Contractor Agreements Engage before agreement due to contract negotiation. 2. Construction Engage when the project begin due to the importance of contribution in construction. 3. Reporting and Documentation Engage because of information known by contractor.	Interactive Communication Media: Meetings, information board, video call, phone call, instant messaging, e-mail, cloud storage, fax, annual report


N. Risk Analysis

Risk analysis is developed qualitatively and quantitatively. Below is the list of selected qualitative risk analysis and response plan (Full list and explanation in [Appendix F](#)).

Risk Identification				Qualitative Analysis				Response Plan
Code	Impacted Phase	Risk	Cause	P	I	Risk Rate	Threat/ Opportunity	
RG08	Whole Project in General	Stakeholders Conflict	Bad Communication Plan, Information Misunderstanding	0.20	0.20	0.06	Threat	Mitigate, Avoid
RG09		Low on Budget	Bad Project Plan, Bad Project Process, Bad Investors Plan, Unexpected Events, Higher Budget Expenses	0.70	0.30	0.56/High	Threat	Transfer, Mitigate, Avoid
RP01	Planning	Mistake in developing requirements list	Bad Survey Process	0.50	0.80	0.4/High	Threat	Mitigate
RC03	Construction	Work Accident	Bad HSE Implementation	0.50	0.40	0.2/High	Threat	Avoid
RC06		Defect material	Bad Procurement Planning, Bad Supplier, Bad Distribution, Bad Material Handling	0.50	0.80	0.4/High	Threat	Transfer, Mitigate, Avoid
RL02	Legal & Regulation	Resent Workers (Demonstration)	Unaware of Workers Wants & Needs	0.30	0.40	0.12/Medium	Threat	Avoid
RT01	Testing	System Test Failure	Incompatible Process Design, Bad Construction Process	0.50	0.80	0.4/High	Threat	Accept, Mitigate

From the qualitative risk analysis, a three point estimation schedule and cost is developed (respectively available in [Appendix G](#) and [Appendix H](#)). The three point estimation is analyzed

further in a Monte Carlo Simulation. The result of Monte Carlo Simulation is available in the figures below.




Based on the Monte Carlo simulation results, with expectation for likelihood of project success 95% the contingency reserve for this project should be 163 days and IDR 568,090,436,000

O. References

- Aziza, K. S. (2014, February 8). *Pengelolaan Sampah Merugi, DKI Putus Kontrak dengan Swasta* . Retrieved from Kompas.com: <http://megapolitan.kompas.com/read/2014/02/08/1213426/Pengelolaan.Sampah.Merugi.DKI.Putus.Kontrak.dengan.Swasta>
- Badan Pendapatan Daerah DKI Jakarta. (2012, January 12). Peraturan Daerah Provinsi Daerah Khusus Ibukota Jakarta Nomor 1 Tahun 2012 Tentang Rencana Tata Ruang Wilayah 2030. Jakarta, DKI Jakarta, Indonesia.
- Project Management Institute. (2013). *A Guide To The Project Management Body of Knowledge* (5th ed.). Newtown Sqaure: Project Management Institute.
- Purnamasari, D. D. (2016, January 8). *Warga Desak Segera Sosialisasi ITF, DKI Masih Mengkaji*. Retrieved from Kompas.com: <http://print.kompas.com/baca/2016/01/08/Warga-Desak-Segera-Sosialisasi-ITF%2c-DKI-Masih-Meng>

Appendix A. Jakarta Development Plan Map




Jakarta Development Map (Retrieved from: Regulation for Daerah Provinsi Daerah Khusus Ibukota Jakarta Number 1 Year 2012 about Layout Plan 2030)


Legend of Jakarta Development Map

Shading	Land Usage	Shading	Land Usage
	Mangrove/ Preserved Forrest		Agriculture/ Livestock
	Cleared Space/ Graveyard		Industry/ Warehousing
	Governmental Area		Lake/ Swamp/ Pond
	Organized Residence		Social Facility
	Unorganized Residence		Transportation Ports (Harbor/Airport)
	Offices/ Service Commerce		Free Space


[Back to Chapter B. Background](#)


Appendix B. Project Schedule






Appendix C. Project Milestone







[Back to Chapter K. Project Time](#)

Appendix D. Budget List

Activity Based Cost Budget					
Resource Name	Max. Units	Standard Rate (IDR/mon)	Overtime Rate (IDR/hour)	Usage Time (hour)	Total Cost (IDR)
Project Manager	1	44,996,000	336,000	4,304	1,210,398,000
Project Engineer	3	14,994,000	112,000	12,912	1,210,020,000
Main Contractor	1	9,996,000	70,000	3,456	215,908,000
Sub-Contractor	10	7,000,000	56,000	3,968	173,600,000
Finance and Administration	4	9,996,000	70,000	17,216	1,075,564,000
Surveyor	3	6,006,000	42,000	624	23,422,000
Procurement	2	9,996,000	70,000	3,456	215,908,000
Architect	2	7,000,000	56,000	7,360	322,000,000
Engineer	5	7,000,000	56,000	11,216	490,700,000
Sub-Total					4,937,520,000
Usage Based Cost Budget					
Resource Name		Cost/Unit (IDR)	Supporting Cost (IDR)	Units Needed	Total Cost (IDR)
MSW Recycling Package		150,000,004,000	24,654,000	1 Pack	150,024,658,000
Extruding Machine		1,999,998,000	6,160,000	1 Pack	2,006,158,000
Leftover Waste Dryer		1,999,998,000	6,160,000	1 Pack	2,006,158,000
Forklift		538,804,000	3,500,000	4 Unit	2,158,702,000
Building Material (Site Development)		190,470,000	7,504,000	1 Pack	197,974,000
Building Material (Civil Structures)		609,518,000	7,504,000	1 Pack	617,022,000
Bailing Machine		140,000,000	6,160,000	5 Unit	706,160,000
Wire Machine		168,000,000	6,160,000	5 Unit	846,160,000
Fertilizer Packaging System		316,400,000	6,160,000	1 Pack	322,560,000
Fix Fence		294,000	798,000	2,000 m	600,838,000
CCTV		994,000	504,000	25 Unit	25,508,000
Personal Computer		4,998,000	1,204,000	24 Unit	121,198,000
Security System		20,006,000	3,500,000	1 Pack	23,506,000
Electricity Installment		14,994,000	9,996,000	1 Pack	25,004,000
Generator Set		884,800,000	6,160,000	1	890,960,000
Communication Package		20,006,000	7,994,000	1 Pack	28,000,000
Conveyor		1,400,000	6,160,000	800 m	1,126,160,000
Sorting System Installment		6,500,004,000	24,654,000	1 Pack	6,524,644,000
Plumbing System		676,004,000	7,994,000	1 Pack	684,012,000
Smart Thermal System		67,004,000	130,004,000	1 Pack	196,994,000
Land and Land Acquisition		7,910,000	334,684,000	250,000 m²	1,977,834,684,000
Sub-Total					2,146,967,060,000
Undistributed Cost Budget					
Resource Name			Accrue at		Cost (IDR)
Documentation			Documentation		2,436,000
Report Writing			Report Writing		938,000
Report Publishing			Report Publishing		1,610,000
Sub-Total					4,984,000
Performance Measurement Baseline (701 days)					2,151,909,564,000

[Back to Chapter L. Master Budget](#)

Appendix E. Stakeholder Analysis

ID	Stakeholder	Description	Power (Level 1-10)	Interest (Level 1-10)	Engagement Phase	Communica tion Plan
A	Investor	Peoples who invest money in this project	High (8) 1. Have a right to change project plan due to funding 2. Responsible for financial support	Moderate (6) 1. Project Objectives	Whole Project Phase Will be engage at the beginning of the project due to the importance of investment and also given annual reports until project finish.	Interactive Communication Media: Meetings, video conference, e-mail, cloud storage, fax, annual report
B	DKI Jakarta Government	Main authority owner	Very High (10) 3. Have a right to change project plan 4. Responsible for agreement	Very High (10) 5. Project Plan 6. Project Progress and Report 7. Cleaner Jakarta 8. Project Objectives	Whole Project Phase Will be engage at the beginning of the project due to the importance of waste management , regulatory, and also given annual reports until project finish.	Interactive Communication Media: Meetings, video conference, e-mail, cloud storage, fax annual report
C	Sanitary Department of DKI Jakarta	Authority owner for all waste activities in DKI Jakarta	Very High (9) 1. Have a right to change project plan 2. Responsible for waste management	Very High (10) 1. Project Plan 2. Project Progress and Report 3. Cleaner Jakarta 4. Better waste management system	Whole Project Phase Will be engage at the beginning of the project due to the importance of waste management , the process of treatment, and also the	Interactive Communication Media: Meetings, video conference, e-mail, cloud storage, fax, annual report

ID	Stakeholder	Description	Power (Level 1-10)	Interest (Level 1-10)	Engagement Phase	Communica tion Plan
					output treatment.	
D	Regional Development Agency of DKI Jakarta	Authority owner for the development of DKI Jakarta	Very High (9) 1. Have a right to change project plan regarding to location and ITF size 2. Responsible for waste management	High (8) 1. Project Plan 2. Project Progress and Report 3. Project Objectives	Whole Project Phase Will be engage at the beginning of the project due to the importance all of building and land regulation.	Interactive Communica tion Media: Meetings, video conference, e-mail, cloud storage, fax, annual report
E	Environment Department of DKI Jakarta	Authority owner who evaluate and control environmental and pollution issues in DKI Jakarta	Very High (9) 1. Have a right to change project plan 2. Responsible for waste management	Very High (10) 1. Project Plan 2. Project Progress and Report 3. Cleaner Jakarta 4. Better waste managemen t system	Whole Project Phase Will be engage at the beginning of the project due to the importance of sustainability development in the city.	Interactive Communica tion Media: Meetings, video conference, e-mail, cloud storage, fax, annual report
F	Transportation Department of DKI Jakarta	Authority owner for transportation modes in DKI Jakarta	Moderate (5) 1. Have a right to change project plan due to transportation methods of materials	Low (4) 1. Project Schedule 2. Material List	Distribution Activity The engagement at the beginning tools, equipment, materials, in the before, during, and after the project.	Pull Communica tion Media: Meetings, instant messaging, e-mail, fax, phone
G	Ministry of Labor	Highest institution authorized for labor in Indonesia	Moderate (5) 1. Have a right to change project plan due to labor usage, rate, safety, and health	Low (3) 1. Project Labor Usage	Whole project phase Will be engage at the beginning of	Push Communica tion Media: e-mail, fax, phone

ID	Stakeholder	Description	Power (Level 1-10)	Interest (Level 1-10)	Engagement Phase	Communica tion Plan
					the project due to the contractor agreements and work agreements	
H	Ministry of Environment	Highest institution authorized for environmental, waste, and pollution issues in Indonesia	High (8) 1. Have a right to change project plan 2. Responsible for waste management	High (8) 1. Project Plan 2. Project Progress and Report 3. Better waste management system	Whole project phase Will be engage at the beginning and at the middle of the project due to the legal and regulatory, testing, reporting and documentation	Pull Communication Media: Meetings, e-mail, fax, phone
I	Ministry of Coordination for Economy	Highest institution authorized for the economic growth in Indonesia	Moderate (5) 1. Responsible for economic impact of the project	High (7) 1. Project Plan 2. Project Progress and Report 3. Cleaner Jakarta 4. Project Objectives	Whole project phase Will be engage at the beginning, the process, and the end of the project due to the legal and regulatory, testing, reporting and documentation	Pull Communication Media: Meetings, e-mail, fax, phone
J	Ministry of Energy and Mineral Resources	Highest Institution authorized for the energy and mineral resource usage in Indonesia	Moderate (5) 1. Responsible for energy regulation of the facility	High (7) 1. Project Plan 2. ITF Partnership due to energy production	Whole Project Phase Will be engage at the beginning of the project due to the	Pull Communication Media: Meetings, e-mail, fax, phone

ID	Stakeholder	Description	Power (Level 1-10)	Interest (Level 1-10)	Engagement Phase	Communica tion Plan
					Licensing, Testing, and also Reporting and Documentati on	
K	Pembangkit Listrik Negara (PLN)	Institution responsible for the generating electricity in Indonesia	Very High (10) 1. Responsible for electrical installation and usage in the facility	High (8) 1. Project Plan 2. Project Schedule 3. ITF Partnership due to electrical energy production	1. Licensing Engage in the beginning of the project due to obtain power plant permission. 2. Cooperation Engage when the power plant already established for electricity business purpose.	Pull Communication Media: Meetings, e-mail, fax, phone
L	Citizen of DKI Jakarta	Society who lives in DKI Jakarta and mainly generates waste	Very Low (1) 2. Affect Political Decisions	Moderate (6) 3. Cleaner Jakarta 4. Project Progress and Report	Whole Project Phase Will be engage at the beginning until the end of the project due to the project information transparency.	Push Communication Media: Television, radio, newspaper, websites, annual reports
M	Main Contractors	Person responsible for the whole construction site activity	Very High (10) 2. Responsible for the whole construction phase	Very High (9) 4. Project Plan 5. Project Progress and Report 6. Project Objective	1. Contractor Agreements Engage before agreement due to contract negotiation. 2. Construction	Interactive Communication Media: Meetings, information board, video call, phone call, instant messaging, e-mail,

ID	Stakeholder	Description	Power (Level 1-10)	Interest (Level 1-10)	Engagement Phase	Communica tion Plan
					Engage when the project begin due to the importance of contribution in construction. 3. Reporting and Document ation Engage because of information known by contractor.	cloud storage, fax, annual report
N	Subsidiary Contractors	People hired by main contractor to handle specialized activity in the construction site	Very High (9) 1. Responsible for the specialized construction phase	High (8) 1. Project Plan 2. Project Progress and Report 3. Project Objective	1. Contractor Agreement s Engage before agreement due to contract negotiation. 2. Constructi on Engage when the project begin due to the importance of contribution in construction. 3. Reporting and Document ation Engage because of information known by contractor.	Interactive Communica tion Media: Meetings, information board, video call, phone call, instant messaging, e-mail, cloud storage, fax, annual report

ID	Stakeholder	Description	Power (Level 1-10)	Interest (Level 1-10)	Engagement Phase	Communica tion Plan
O	Architect	Person responsible for the architectural design of facility	High (8) 1. Responsible for the grand design of the facility	High (7) 1. Project Plan 2. Project Progress and Report 3. Project Objective	1. Constructi on Planning Engage before the project due to the building design. 2. Constructi on Engage during the project due to the importance of the project progress and synchronizati on design and the actual construction. 3. Reporting and Document ation Engage because of the importance of writing.	Interactive Communica tion Media: Meetings, information board, video call, phone call, instant messaging, e-mail, cloud storage, fax, annual report
P	Engineers	People responsible for particular technical activities such as software installations, drainage system, work SOP, electricity system, communication s system, etc.	High (8) 1. Responsible for the technical aspects of the facility	High (7) 1. Project Plan 2. Project Progress and Report 3. Project Objective	1. Constructi on Planning Engage before the project due to the technical design. 2. Constructi on Engage during the project due to the	Interactive Communica tion Media: Meetings, information board, video call, phone call, instant messaging, e-mail, cloud storage, fax,

ID	Stakeholder	Description	Power (Level 1-10)	Interest (Level 1-10)	Engagement Phase	Communica tion Plan
					importance of the project progress and synchronization on technical requirements and the actual construction. 3. Reporting and Documentation Engage because of the importance of writing.	annual report
Q	Construction Workers	People who are directly working for the construction	High (7) 1. Responsible for the construction activity of the facility	Moderate (6) 1. Project Plan 2. Project Progress and Report	1. Work Agreements Engage before the agreement due to the negotiation. 2. Construction Engage during the construction due to the construction work.	Pull Communication Media: Meetings, information board, e-mail, phone call
R	Material Suppliers	Source of material	Very High (10) 1. Responsible for construction material procurement	Moderate (5) 1. Project Schedule 2. Material List	1. Construction Planning Engage before construction due to material supply agreements. 2. Construction	Interactive Communication Media: Meetings, video call, phone call, instant messaging, e-mail, fax, bill of material

ID	Stakeholder	Description	Power (Level 1-10)	Interest (Level 1-10)	Engagement Phase	Communication Plan
					Engage during the construction due to the importance of material arrival and quality.	
S	Customs	Institution responsible to handle distribution tax and customs from overseas countries	High (7) 1. Responsible for construction material distribution from overseas	Moderate (5) 1. Project Schedule 2. Material List	Construction Engage before the construction due to the tax and material importance.	Pull Communication Media: Meetings, e-mail, fax, phone
T	Nearby Private ITFs	Institutes in the ITF business which aren't owned by the government	Very Low (2) 1. Support/hamper ITF development	Moderate (5) 1. ITF Partnership	Partnership Engage if interested in cooperation of the project construction or product.	Push Communication Media: website
U	United Nations Environment Programme (UNEP)	Institution owned by The UN related to chemical and waste management	Moderate (5) 1. Responsible for policy advice, technical guidance related to waste management	High (7) 1. Promotes chemical safety and waste management	1. Construction Planning Engage before the project due to sustainability. 2. Legal and Regulatory Engage before the project due to the policy and regulatory importance. 3. Reporting and Documentation Engage if investment funding in	Pull Communication Media: Meetings, e-mail, fax, phone, progress report

ID	Stakeholder	Description	Power (Level 1-10)	Interest (Level 1-10)	Engagement Phase	Communica tion Plan
					the project. Thus, will be given project progress and information.	
W	Other Countries (Malaysia, Singapore, Japan, Germany, etc.)	Possible stakeholders who may be involved in the project from outside of Indonesia	Moderate (5) 1. Provide aid 2. Affect political decisions	Moderate (5) 1. ITF Partnership 2. Project partnership	Partnership Engage if interested in cooperation of the project construction or product.	Push Communica tion Media: website
V	Other Districts around Jakarta (Banten and West Java)	Nearby districts that may be involved in the projects	Moderate (5) 1. Provide aid 2. Affect political decisions	Moderate (5) 1. ITF Partnership 2. Project partnership	Partnership Engage if interested in cooperation of the project construction or product.	Push Communica tion Media: website
X	Future Cilincing ITF Managers	Future team of people who will manage ITF in Cilincing	Very Low (2) 1. Future Project Team 2. Future Operation Team	Very High (9) 1. Project Objectives 2. ITF system 3. Project Progress and Report	Reporting and Documentati on Engage during the project due to the start of ITF operation date.	Push Communica tion Media: Phone, e- mail, fax, website, progress report
Y	Regional Police Station	Regional police station in case of extra security is needed	Moderate (5) 1. Provide security	Moderate (6) 1. Project Progress 2. Project Schedule	Whole Project Phase Engage before and during the project due to the activity permit and security.	Push Communica tion Media: Phone, e- mail, fax
Z	Nearby Hospitals	Nearby hospitals in case of emergency	Moderate (5) 1. Take care of labor when they are not in a good condition	Moderate (6) 1. Project Objective	Whole Project Phase Engage before and	Push Communica tion Media:

ID	Stakeholder	Description	Power (Level 1-10)	Interest (Level 1-10)	Engagement Phase	Communica tion Plan
					during the project due to the HSE importance.	Phone, e-mail, fax
AA	Nearby Firefighter Station	Nearby firefighter case of fire emergency	Moderate (5) 1. Responsible for firefighting emergency	Moderate (6) 1. Project Objective	Whole Project Phase Engage before project due to the HSE importance and also emergency accident.	Push Communication Media: Phone, e-mail, fax
AB	Merak Port	Nearby port which could possibly the material distribution channel via ship	Moderate (5) 1. Responsible for material distribution via ship	High (8) 1. Project Schedule 2. Material List	Construction Engage before and during the project due to the material distribution.	Push Communication Media: Phone, e-mail, fax
AC	Halimperdana Kusuma Airport	Nearby airport which could possibly the material distribution channel via airplane	Moderate (5) 1. Responsible for material distribution via airplane	High (8) 1. Project Schedule 2. Material List	Construction Engage before and during the project due to the material distribution.	Push Communication Media: Phone, e-mail, fax
AD	Local Labor Insurance Institution	Institution responsible for labor insurance	Moderate (5) 1. Responsible for labor insurance	High (8) 1. Project Schedule 2. Material List	1. Work Agreements 2. Construction Engage before and during the project due to HSE importance.	Push Communication Media: Phone, e-mail, fax
AE	Citizen nearby Bantargebang	Citizens who live near Bantargebang	Low (3) 1. Affect political decisions	Moderate (5) 1. Project Objective	Whole Project Phase Will be engage at the beginning	Push Communication Media: website

ID	Stakeholder	Description	Power (Level 1-10)	Interest (Level 1-10)	Engagement Phase	Communica tion Plan
					until the end of the project due to the project information transparency.	
AF	Journalist	Journalist who makes news for TV, radio, newspaper, etc.	Moderate (5) 1. Publish the information about ITF to society	High (8) 1. Project Schedule	Whole Project Phase Engage during and after the project due to the reporting and documentation.	Push Communication Media: Electronic and printed
AG	Notary	Third-party who is responsible in giving land acquisition certifications.	Very High (9) 1. Land acquisition must not be late	Moderate (6) 1. Money 2. Fame	Land acquisition Engage before and during land acquisition due to the land acquisition importance.	Pull Communication Media: e-Mail, direct meeting and printed documents

[Back to Chapter M. Stakeholder Analysis](#)

Appendix F. Qualitative Risk Analysis

Risk Identification				Qualitative Analysis				Response Plan					Risk Residual			Response Plan Priority	
Code	Impacted Phase	Risk	Cause	P	I	Risk Rate	Threat/ Opportunity	Possible Risk Response	Response Application Plan	Response Plan Impact	PIC of Response Plan	Expected Actions from PIC	P	I	Risk Residual Rate	Priority Rate	Priority Level
RG01	Whole Project in General	Higher Budget Expenses	Dollar Price Against Rupiah Increase, Failure in Bargaining	0.50	0.80	0.4 /High	Threat	Accept	Accept Price Increase when crucial	Higher Budget Expenses	Project Manager, Project Engineer, Finance and Administration	Define new cost baseline	0.90	0.80	0.72 /High	0.03	Very Low (4)
								Mitigate	Reduce Human Resource Usage	Stable Cost, Late Schedule	Project Manager, Project Engineer, Contractor	Define subcontract schedule and resource plan	0.10	0.20	0.02 /Low	0.97	Very High (2)
											Finance and Administration	Prepare updated budget baseline					
								Avoid	Subcontract work before cost occur	Stable cost expenses	Project Manager, Project Engineer, Contractor	Define subcontract schedule and resource plan	0.10	0.10	0.01 /Low	1.00	Top Priority (1)
											Finance and Administration	Prepare updated budget baseline					
									Change product scope	Project plan change	Project Manager	Hold meeting with stakeholders to inform and discuss plan change	0.30	0.40	0.12 /Medium	0.72	High (3)
RG02		Resource Usage Increase	Schedule Change, Project Plan Change	0.50	0.80	0.4 /High	Threat	Avoid	Subcontract work based on task quality, not duration	Stable schedule, Stable Resource Usage	Project Manager, Project Engineer, Engineer, Procurement, Contractor	Define subcontract schedule and resource plan	0.10	0.10	0.01 /Low	1.00	Top Priority (1)

Risk Identification				Qualitative Analysis				Response Plan					Risk Residual			Response Plan Priority	
Code	Impacted Phase	Risk	Cause	P	I	Risk Rate	Threat/ Opportunity	Possible Risk Response	Response Application Plan	Response Plan Impact	PIC of Response Plan	Expected Actions from PIC	P	I	Risk Residual Rate	Priority Rate	Priority Level
RG03											Finance and Administration	Prepare updated budget baseline					
								Accept	Accept Usage Increase	Resource usage increase	Project Manager, Project Engineer, Contractor	Define new cost, schedule, and resource baseline	0.90	0.80	0.72 /High	0.03	Very Low (2)
											Finance and Administration	Prepare updated budget baseline					
		Lower Budget Expenses	Dollar Price Against Rupiah Decrease, Successful Bargaining	0.30	0.40	0.12 /Medium	Opportunity	Share	Hire more workers to balance with cost budget	Early schedule	Project Manager, Project Engineer, Contractor	Define updated schedule and resource, and cost plan	0.50	0.80	0.4 /High	0.47	Low (2)
											Finance and Administration	Prepare updated budget baseline					
								Exploit	Subcontract Work when cost decrease occur	Lower Budget Expenses	Project Manager, Project Engineer, Contractor	Define subcontract schedule and resource plan	0.90	0.80	0.72 /High	1.00	Top Priority (1)
											Finance and Administration	Prepare updated budget baseline					
RG04		Resource Usage Decrease	Schedule Change, Project Plan Change, Better Technology, Better Method, Better Human Resources	0.30	0.40	0.12 /Medium	Opportunity	Exploit	Subcontract work based on task quality, not duration	Stable schedule	Project Manager, Project Engineer, Contractor	Define subcontract schedule and resource plan	0.70	0.80	0.56 /High	1.00	Top Priority (1)
											Finance and Administration	Prepare updated budget baseline					
								Enhance	Balancing activity	Schedule change	Project Manager,	Define updated	0.30	0.40		0.02	

Risk Identification				Qualitative Analysis				Response Plan					Risk Residual			Response Plan Priority	
Code	Impacted Phase	Risk	Cause	P	I	Risk Rate	Threat/ Opportunity	Possible Risk Response	Response Application Plan	Response Plan Impact	PIC of Response Plan	Expected Actions from PIC	P	I	Risk Residual Rate	Priority Rate	Priority Level
									duration with resource usage		Project Engineer, Contractor	schedule and resource, and cost plan			0.12 /Medium		Very Low (2)
											Finance and Administration	Prepare updated budget baseline					
			Low on Budget	0.70	0.40	0.28 /High	Threat	Accept	Keep working on project	Reduced resources usage, late schedule	Project Manager, Project Engineer, Contractor	Define new schedule and resource plan	0.90	0.40	0.36 /High	0.04	Very Low (6)
											Finance and Administration	Prepare updated budget baseline					
								Transfer	Search for new investors	Extra capital, new stakeholder	Project Manager	Search for new investors	0.50	0.20	0.1 /Medium	0.72	High (2)
								Mitigate	Ask for extra capital funding from current stakeholders	Extra capital	Project Manager	Hold meeting with current stakeholders for extra capital funding	0.30	0.10	0.03 /Low	1.00	Top Priority (1)
								Avoid	Cancel project	Project fail	Project Manager	Cancel project	0.10	0.80	0.08 /Medium	0.01	Very Low (7)
									Temporary project shut down	Late schedule	Project Manager, Project Engineer, Contractor	Define new schedule, resource, and cost baseline	0.50	0.40	0.2 /High	0.32	Low (4)
											Finance and Administration	Prepare updated budget baseline					
									Activity postpone	Late schedule	Project Manager, Project Engineer, Contractor	Define new schedule, resource, and cost baseline	0.50	0.20	0.1 /Medium	0.72	High (2)

Risk Identification				Qualitative Analysis				Response Plan					Risk Residual			Response Plan Priority	
Code	Impacted Phase	Risk	Cause	P	I	Risk Rate	Threat/ Opportunity	Possible Risk Response	Response Application Plan	Response Plan Impact	PIC of Response Plan	Expected Actions from PIC	P	I	Risk Residual Rate	Priority Rate	Priority Level
RG05											Finance and Administration	Prepare updated budget baseline	0.50	0.40	0.2/High	0.32	Low (4)
											Project Manager	Hold meeting with stakeholders to inform and discuss plan change					
		Early Schedule	Bad Planning	0.10	0.80	0.08/Medium	Threat	Avoid	Subcontract work	Stable schedule	Project Manager, Project Engineer, Engineer, Procurement, Contractor	Define subcontract schedule and resource plan	0.10	0.20	0.02/Low	1.00	Top Priority (1)
			Technology Development, High Quality Resource	0.30	0.40	0.12/Medium	Opportunity	Enhance	Balance upcoming activity duration and resource	Stable schedule	Finance and Administration	Prepare updated budget baseline					
											Project Manager, Project Engineer, Contractor	Define new schedule and resource plan	0.50	0.80	0.4/High	0.64	Medium (2)
									Use new technology and/ or high quality resource when available	Satisfied stakeholders due to faster schedule, human resource usage decrease	Finance and Administration	Prepare updated budget baseline					
											Project Manager, Project Engineer, Contractor	Define new schedule and resource plan	0.70	0.80	0.56/High	1.00	Top Priority (1)
											Procurement	Ensure new technology is available					
RG06		Late Schedule	Bad Weather, Low Budget, Bad Project	0.70	0.40	0.28/High	Threat	Avoid	Subcontract work	Stable schedule	Project Manager, Project	Define subcontract schedule	0.10	0.05	0.01/Low	1.00	Top Priority

Risk Identification				Qualitative Analysis				Response Plan					Risk Residual			Response Plan Priority	
Code	Impacted Phase	Risk	Cause	P	I	Risk Rate	Threat/ Opportunity	Possible Risk Response	Response Application Plan	Response Plan Impact	PIC of Response Plan	Expected Actions from PIC	P	I	Risk Residual Rate	Priority Rate	Priority Level
			Plan, Temporary shutdown, Activity postpone								Engineer, Engineer, Procurement, Contractor	and resource plan					Very Low (1)
											Finance and Administration	Prepare updated budget baseline					
											Project Manager, Project Engineer, Contractor	Define overtime schedule and resource plan	0.30	0.20	0.06 /Medium	0.81	High (4)
											Finance and Administration	Prepare updated budget baseline					
											Project Manager	Hold meeting with current stakeholders for extra capital funding	0.50	0.10	0.05 /Low	0.85	High (3)
											Project Manager	Search for new investors	0.70	0.40	0.28 /High	0.04	Very Low (5)
											Project Manager, Project Engineer, Contractor	Define outsourcing schedule and resource plan	0.10	0.20	0.02 /Low	0.96	Very High (2)
											Finance and Administration	Prepare updated budget baseline					
											Project Manager, Project Engineer, Contractor	Define late schedule and resource plan	0.90	0.40	0.36 /High	0.01	Very Low (6)
											Finance and Administration	Prepare updated					

Risk Identification				Qualitative Analysis				Response Plan					Risk Residual			Response Plan Priority	
Code	Impacted Phase	Risk	Cause	P	I	Risk Rate	Threat/ Opportunity	Possible Risk Response	Response Application Plan	Response Plan Impact	PIC of Response Plan	Expected Actions from PIC	P	I	Risk Residual Rate	Priority Rate	Priority Level
												budget baseline					
RG07		Project Plan Change	External Influence (Politics, Society, Competitors, Investors), Low on Budget, Late Schedule, Early Schedule, Scope Change	0.50	0.80	0.4 /High	Threat	Avoid	Urge stakeholders to cancel plan change by informing about the loss from the change	Schedule change and/or stakeholder conflict	Project Manager	Hold stakeholder meeting	0.30	0.40	0.12 /Medium	0.76	High (2)
									Determine important milestones of the project	Clear project plan	Project Manager, Project Engineer, Engineers, Contractors	Set project milestones	0.30	0.10	0.03 /Low	1.00	Top Priority (1)
				0.30	0.40	0.12 /Medium	Opportunity	Exploit	If profitable directly inform stakeholders to ensure plan change occur	Better technology usage, better human resource, faster schedule, less expenses, etc.	Project Manager	Hold stakeholder meeting to implement the better technology in the project	0.70	0.40	0.28 /High	1.00	Top Priority (1)
RG08		Stakeholders Conflict	Bad Communication Plan, Information Misunderstanding	0.30	0.20	0.06	Threat	Mitigate	Directly communicate with the conflicting stakeholders to solve the conflict	Postponed project or late schedule in order to solve conflict	Project Manager	Hold stakeholder meeting	0.30	0.10	0.03 /Low	0.60	Medium (2)
								Avoid	Ensure the stakeholders understand clearly the information given	Reduced stakeholder conflict probability	Project Manager, Project Engineer	Utilize the best communication method with each stakeholders	0.10	0.10	0.01 /Low	1.00	Top Priority (1)
RG09		Low on Budget	Bad Project Plan, Bad Project Process, Bad Investors Plan, Unexpected Events, Higher	0.70	0.80	0.56 /High	Threat	Transfer	Search for new investors	Extra capital, new stakeholder	Project Manager	Search for new investors	0.50	0.20	0.1 /Medium	0.87	High (2)
								Mitigate	Ask for extra capital funding from	Extra capital	Project Manager	Hold meeting with current stakeholders	0.30	0.10	0.03 /Low	1.00	Top Priority (1)

Risk Identification				Qualitative Analysis				Response Plan					Risk Residual			Response Plan Priority	
Code	Impacted Phase	Risk	Cause	P	I	Risk Rate	Threat/ Opportunity	Possible Risk Response	Response Application Plan	Response Plan Impact	PIC of Response Plan	Expected Actions from PIC	P	I	Risk Residual Rate	Priority Rate	Priority Level
			Budget Expenses						current stakeholders			for extra capital funding					
								Avoid	Cancel project	Project fail	Project Manager	Cancel project	0.10	0.80	0.08 /Medium	0.02	Very Low (6)
									Temporary project shut down	Late schedule	Project Manager, Project Engineer, Contractor	Define new schedule, resource, and cost baseline	0.50	0.40	0.2 /High	0.68	Medium (4)
											Finance and Administration	Prepare updated budget baseline					
									Activity postpone	Late schedule	Project Manager, Project Engineer, Contractor	Define new schedule, resource, and cost baseline	0.50	0.20	0.1 /Medium	0.87	High (2)
											Finance and Administration	Prepare updated budget baseline					
									Project Scope Change	Project plan change	Project Manager	Hold meeting with stakeholders to inform and discuss plan change	0.50	0.40	0.2 /High	0.68	Medium (4)
RPO 1	Planning	Mistake in developing requirements list	Bad Survey Process	0.50	0.80	0.4 /High	Threat	Mitigate	Simulate the system based on existing ITFs	Better construction planning	Project Manager, Project Engineer, Engineer, Contractor, Surveyor, Architect	Do simulation and plan based on simulation result	0.30	0.10	0.03 /Low	1.00	Top Priority (1)
RPO 2		Mistake in developing process modeling	Bad Requirements List	0.50	0.80	0.4 /High	Threat	Mitigate	Build process model based on simulation result	Better construction planning	Project Manager, Project Engineer, Engineer, Contractor, Surveyor, Architect	Do simulation and plan based on simulation result	0.30	0.10	0.03 /Low	1.00	Top Priority (1)

Risk Identification				Qualitative Analysis				Response Plan					Risk Residual			Response Plan Priority	
Code	Impacted Phase	Risk	Cause	P	I	Risk Rate	Threat/ Opportunity	Possible Risk Response	Response Application Plan	Response Plan Impact	PIC of Response Plan	Expected Actions from PIC	P	I	Risk Residual Rate	Priority Rate	Priority Level
RC01	Construction	Faster Construction Process	Bad Planning, Technology Development	0.10	0.80	0.08 /Medium	Threat	Avoid	Subcontract work carefully	Stable schedule	Project Manager, Project Engineer, Engineer, Procurement, Contractor	Define subcontract schedule and resource plan	0.10	0.20	0.02 /Low	1.00	Top Priority (1)
											Finance and Administration	Prepare updated budget baseline					
								Mitigate	Revise work schedule	Stable schedule	Project Manager, Project Engineer, Contractor	Define revised schedule and resource plan	0.30	0.20	0.06 /Medium	0.33	Low (2)
											Finance and Administration	Prepare updated budget baseline					
			Technology Development, High Quality Resource	0.30	0.40	0.12 /Medium	Opportunity	Accept	Accept the faster construction process	Extra activity based cost due to unused human resources	Finance and Administration	Prepare updated budget baseline	0.90	0.40	0.36 /High	0.17	Very Low (3)
								Enhance	Balance upcoming activity duration and resource	Stable schedule	Project Manager, Project Engineer, Contractor	Define new schedule and resource plan	0.50	0.80	0.4 /High	0.64	Medium (2)
											Finance and Administration	Prepare updated budget baseline					
								Exploit	Use new technology and/ or high quality resource when available	Satisfied stakeholders due to faster schedule, human resource	Project Manager, Project Engineer, Contractor	Define new schedule and resource plan	0.70	0.80	0.56 /High	1.00	Top Priority (1)
											Procurement	Ensure new technology is available					

Risk Identification				Qualitative Analysis				Response Plan					Risk Residual			Response Plan Priority	
Code	Impacted Phase	Risk	Cause	P	I	Risk Rate	Threat/ Opportunity	Possible Risk Response	Response Application Plan	Response Plan Impact	PIC of Response Plan	Expected Actions from PIC	P	I	Risk Residual Rate	Priority Rate	Priority Level
										usage decrease	Finance and Administration	Prepare updated budget baseline					
RCO 2		Late Construction Process	Bad Weather, Low Budget, Bad Project Plan, Temporary shutdown, Activity postpone, Bad Procurement	0.70	0.80	0.56 /High	Threat	Avoid	Subcontract work	Stable schedule	Project Manager, Project Engineer, Engineer, Procurement, Contractor	Define subcontract schedule and resource plan	0.10	0.05	0.01 /Low	1.00	Top Priority (1)
											Finance and Administration	Prepare updated budget baseline					
								Mitigate	Overtime to balance schedule	Extra cost, unsatisfied worker	Project Manager, Project Engineer, Contractor	Define overtime schedule and resource plan	0.30	0.20	0.06 /Medium	0.91	Very High (4)
											Finance and Administration	Prepare updated budget baseline					
								Transfer	Ask for extra capital funding from current stakeholders	Extra capital	Project Manager	Hold meeting with current stakeholders for extra capital funding	0.50	0.10	0.05 /Low	0.93	Very High (3)
									Search for new investors	Extra capital, new stakeholder	Project Manager	Search for new investors	0.70	0.40	0.28 /High	0.51	Medium (5)
								Transfer	Outsourcing to balance schedule	Extra cost	Project Manager, Project Engineer, Contractor	Define outsourcing schedule and resource plan	0.10	0.20	0.02 /Low	0.98	Very High (2)
											Finance and Administration	Prepare updated budget baseline					

Risk Identification				Qualitative Analysis				Response Plan					Risk Residual			Response Plan Priority	
Cod e	Impacted Phase	Risk	Cause	P	I	Risk Rate	Threat/ Opportunity	Possibl e Risk Respon se	Response Application Plan	Response Plan Impact	PIC of Response Plan	Expected Actions from PIC	P	I	Risk Residu al Rate	Priori ty Rate	Priorit y Level
								Accept	Accept the late schedule	Late schedule, human resource usage increase	Project Manager, Project Engineer, Contractor	Define late schedule and resource plan	0.90	0.40	0.36 /High	0.01	Very Low (6)
										Finance and Administrati on	Prepare updated budget baseline						
RCO 3		Work Accident	Bad HSE Implementation	0.50	0.40	0.2 /High	Threat	Avoid	Remind every stakeholders about the importance of HSE, ensure HSE equipment is in good condition during the project	Safety work, satisfied stakeholders	All stakeholder s	Remind each other about the importance of HSE, ensure HSE equipment is in good condition to use	0.30	0.20	0.06 /Medium	1.00	Top Priorit y (1)
												Project Manager, Project Engineer, Contractor					
																	Give work insurance and do routine medical checkup for every worker in the project (included in work contract)
RCO 4	Late Material Delivery	Bad Procurement Planning	0.50	0.80	0.4 /High	Threat	Accept	Accept the late material delivery	Late schedule, lower expenses (price cur due to late delivery)	Project Manager, Project Engineer, Contractor	Define late schedule and resource plan	0.90	0.80	0.72 /High	0.01	Very Low (5)	
										Finance and Administrati on	Prepare updated						

Risk Identification				Qualitative Analysis				Response Plan					Risk Residual			Response Plan Priority	
Cod e	Impacted Phase	Risk	Cause	P	I	Risk Rate	Threat/ Opportun ity	Possibl e Risk Respon se	Response Application Plan	Response Plan Impact	PIC of Response Plan	Expected Actions from PIC	P	I	Risk Residu al Rate	Priori ty Rate	Priorit y Level
												budget baseline					
								Transfe r	Search for new suppliers	New stakeholder, extra cost, task replanning, late schedule	Procuremen t	Search for new suppliers	0.50	0.80	0.4/High	0.03	Very Low (4)
											Project Manager, Project Engineer, Contractor	Define late schedule and resource plan					
											Finance and Administrati on	Prepare updated budget baseline					
								Transfe r	Outsourcing to balance schedule	Extra cost	Project Manager, Project Engineer, Contractor	Define outsourcing schedule and resource plan	0.50	0.20	0.1/Mediu m	0.77	High (2)
											Finance and Administrati on	Prepare updated budget baseline					
								Mitigat e	Overtime to balance schedule	Extra cost, unsatisfied worker	Project Manager, Project Engineer, Contractor	Define overtime schedule and resource plan	0.50	0.40	0.2/High	0.51	Mediu m (3)
											Finance and Administrati on	Prepare updated budget baseline					
								Avoid	Subcontract material delivery	Stable schedule	Project Manager, Project Engineer, Engineer, Procuremen t, Contractor	Define subcontract schedule and resource plan	0.10	0.05	0.01/Low	1.00	Top Priorit y (1)
											Finance and Administrati on	Prepare updated budget baseline					

Risk Identification				Qualitative Analysis				Response Plan					Risk Residual			Response Plan Priority	
Cod e	Impacted Phase	Risk	Cause	P	I	Risk Rate	Threat/ Opportunity	Possibl e Risk Respon se	Response Application Plan	Response Plan Impact	PIC of Response Plan	Expected Actions from PIC	P	I	Risk Residu al Rate	Priori ty Rate	Priorit y Level
RCO 5		Early Material Delivery	Bad Procurement Planning	0.3 0	0.4 0	0.12 /Mediu m	Threat	Accept	Accept the early material arrival and ensure it is in good condition	Extra cost to keep the material in good condition	Project Manager, Project Engineer, Contractor, Engineer	Provide inventory space for the material and ensure it is in good condition to be used when needed	0.9 0	0.8 0	0.72 /High	0.09	Very Low (5)
								Transfe r	Outsourcing to balance schedule	Extra cost	Project Manager, Project Engineer, Contractor	Define outsourcing schedule and resource plan	0.3 0	0.1 0	0.03 /Low	0.82	High (3)
											Finance and Administrati on	Prepare updated budget baseline					
								Mitigat e	Overtime to balance schedule	Extra cost, unsatisfied worker	Project Manager, Project Engineer, Contractor	Define overtime schedule and resource plan	0.3 0	0.2 0	0.01 /Low	0.55	Mediu m (4)
											Finance and Administrati on	Prepare updated budget baseline					
								Avoid	Subcontract material delivery	Stable schedule	Project Manager, Project Engineer, Engineer, Procuremen t, Contractor	Define subcontract schedule and resource plan	0.1 0	0.0 5	0.01 /Low	1.00	Top Priorit y (1)
											Finance and Administrati on	Prepare updated budget baseline					
									Select the best supplier available	On time delivery	Procuremen t	Select the best supplier available	0.1 0	0.0 5	0.03 /Low	1.00	Top Priorit y (1)
Project Manager,	Define late schedule																

Risk Identification				Qualitative Analysis				Response Plan					Risk Residual			Response Plan Priority	
Code	Impacted Phase	Risk	Cause	P	I	Risk Rate	Threat/ Opportunity	Possible Risk Response	Response Application Plan	Response Plan Impact	PIC of Response Plan	Expected Actions from PIC	P	I	Risk Residual Rate	Priority Rate	Priority Level
											Project Engineer, Contractor	and resource plan					
											Finance and Administration	Prepare updated budget baseline					
			Faster Construction Process, High on Budget	0.30	0.40	0.12 /Medium	Opportunity	Enhance	Balance upcoming activity duration and resource	Stable schedule	Project Manager, Project Engineer, Contractor	Define new schedule and resource plan	0.50	0.80	0.4 /High	0.64	Medium (2)
											Finance and Administration	Prepare updated budget baseline					
								Exploit	Fast forward upcoming activity schedule	Satisfied stakeholders due to faster schedule	Project Manager, Project Engineer, Contractor	Define new schedule and resource plan	0.70	0.80	0.56 /High	1.00	Top Priority (1)
											Procurement	Ensure material is available on time					
RCO 6		Defect Material	Bad Procurement Planning, Bad Supplier, Bad Distribution, Bad Material Handling	0.50	0.80	0.4 /High	Threat	Transfer	Replace defect material from different supplier	New stakeholder, extra cost, task replanning, late schedule	Procurement	Search for new suppliers	0.50	0.80	0.4 /High	0.03	Very Low (5)
											Project Manager, Project Engineer, Contractor	Define late schedule and resource plan					
											Finance and Administration	Prepare updated budget baseline					
									Outsourcing to balance schedule	Extra cost	Project Manager, Project Engineer, Contractor	Define outsourcing schedule and resource plan	0.30	0.20	0.06 /Medium	0.87	High (2)

Risk Identification				Qualitative Analysis				Response Plan					Risk Residual			Response Plan Priority	
Code	Impacted Phase	Risk	Cause	P	I	Risk Rate	Threat/ Opportunity	Possible Risk Response	Response Application Plan	Response Plan Impact	PIC of Response Plan	Expected Actions from PIC	P	I	Risk Residual Rate	Priority Rate	Priority Level
							Threat				Finance and Administration	Prepare updated budget baseline					
								Mitigate	Replace defect material from current supplier	New stakeholder, extra cost, task replanning, late schedule	Procurement	Ask supplier to replace defect material immediately	0.30	0.40	0.12 /Medium	0.72	High (3)
											Project Manager, Project Engineer, Contractor	Define late schedule and resource plan					
											Finance and Administration	Prepare updated budget baseline					
									Overtime to balance schedule	Extra cost, unsatisfied worker	Project Manager, Project Engineer, Contractor	Define overtime schedule and resource plan	0.30	0.40	0.08 /Medium	0.72	High (3)
											Finance and Administration	Prepare updated budget baseline					
								Avoid	Subcontract the best supplier available	Best supply of material available	Project Manager, Project Engineer, Procurement	Select the best supplier available	0.10	0.10	0.01 /Low	1.00	Top Priority (1)
RLO 1	Legal and Regulatory	Contract Fraud	Bad Process and Human Resource	0.50	0.80	0.4 /High	Threat	Avoid	Cancel project	Project fail	Project Manager	Cancel project	0.10	0.80	0.08 /Medium	0.03	Very Low (4)
									Temporary project shut down	Late schedule	Project Manager, Project Engineer, Contractor	Define new schedule, resource, and cost baseline	0.50	0.40	0.2 /High	0.53	Medium (3)
											Finance and Administration	Prepare updated budget baseline					

Risk Identification				Qualitative Analysis				Response Plan					Risk Residual			Response Plan Priority	
Code	Impacted Phase	Risk	Cause	P	I	Risk Rate	Threat/ Opportunity	Possible Risk Response	Response Application Plan	Response Plan Impact	PIC of Response Plan	Expected Actions from PIC	P	I	Risk Residual Rate	Priority Rate	Priority Level
									Activity postpone	Late schedule	Project Manager, Project Engineer, Contractor	Define new schedule, resource, and cost baseline	0.50	0.20	0.1 /Medium	0.79	High (2)
											Finance and Administration	Prepare updated budget baseline					
									Do work contract work carefully	Reduced probability of contract fraud	Project Manager, Project Engineer, Engineer, Procurement, Contractor, Finance and Administration	Read contract carefully before agreement	0.10	0.20	0.02 /Low	1.00	Top Priority (1)
RL02		Resent Workers (Demonstration)	Unaware of Workers Wants & Needs	0.30	0.40	0.12 /Medium	Threat	Avoid	Provide facilities and human resource to ensure worker satisfaction	Reduce probability of resent worker	Project Manager, Project Engineer	Provide the facilities and human resources	0.10	0.10	0.01 /Low	1.00	Top Priority (1)
									Always appreciate workers achievement and give reward for certain milestones from the worker	Reduce probability of resent worker	Project Manager, Project Engineer, Contractor	Appreciate worker and prepare reward for the milestones	0.10	0.10	0.01 /Low	1.00	Top Priority (1)
RL03		Late Land Financing & Acquisition	Bad Process, Low on Budget	0.70	0.80	0.56 /High	Threat	Mitigate	Overtime to balance schedule once land is available	Extra cost	Project Manager, Project Engineer, Contractor	Define new schedule and resource plan	0.50	0.40	0.2 /High	0.71	High (3)
											Procurement	Ensure material is					

Risk Identification				Qualitative Analysis				Response Plan					Risk Residual			Response Plan Priority	
Code	Impacted Phase	Risk	Cause	P	I	Risk Rate	Threat/ Opportunity	Possible Risk Response	Response Application Plan	Response Plan Impact	PIC of Response Plan	Expected Actions from PIC	P	I	Risk Residual Rate	Priority Rate	Priority Level
												available on time					
											Finance and Administration	Prepare updated budget baseline					
								Postpone activity and ask for extra capital funding from current stakeholders	Extra capital	Project Manager	Hold meeting with current stakeholders for extra capital funding		0.50	0.20	0.1 /Medium	0.90	Top Priority (1)
								Postpone activity and search for new investors	Extra capital, new stakeholder	Project Manager	Postpone activity and search for new investors		0.70	0.40	0.28 /High	0.55	Medium (4)
								Transfer	Outsourcing to balance schedule	Extra cost	Project Manager, Project Engineer, Contractor	Define new schedule and resource plan	0.50	0.20	0.1 /Medium	0.90	Top Priority (1)
											Procurement	Ensure material is available on time					
											Finance and Administration	Prepare updated budget baseline					
								Avoid	Cancel project	Project fail	Project Manager	Cancel project	0.70	0.80	0.56 /High	0.02	Very Low (5)
RLO 4		Early Land Financing & Acquisition	Unexpected process	0.50	0.10	0.05 /Low	Opportunity	Exploit	Fast forward upcoming activity schedule	Satisfied stakeholders due to faster schedule	Project Manager, Project Engineer, Contractor	Define new schedule and resource plan	0.70	0.80	0.56 /High	1.00	Top Priority (1)
											Procurement	Ensure material is available on time					
											Finance and Administration	Prepare updated					

Risk Identification				Qualitative Analysis				Response Plan					Risk Residual			Response Plan Priority	
Code	Impacted Phase	Risk	Cause	P	I	Risk Rate	Threat/ Opportunity	Possible Risk Response	Response Application Plan	Response Plan Impact	PIC of Response Plan	Expected Actions from PIC	P	I	Risk Residual Rate	Priority Rate	Priority Level
												budget baseline					
								Accept	Stick to initial plan	Stable schedule	Project Manager, Project Engineer, Contractor	Stick to initial plan	0.50	0.40	0.2 /High	0.29	Low (2)
											Procurement	Ensure material is available on time					
RTO 1	Testing	System Test Failure	Incompatible Process Design, Bad Construction Phase	0.50	0.80	0.4 /High	Threat	Accept	Rework after failure	Extra Cost, late schedule	Project Manager, Project Engineer, Contractor	Define rework schedule and resource plan	0.70	0.80	0.56 /High	0.03	Very Low (3)
											Engineer	Responsible for system failure					
											Procurement	Responsible for material problems in the system failure					
											Finance and Administration	Prepare extra budget for rework					
									Minor repairment after failure	Late schedule	Engineer	Do repairment	0.90	0.40	0.36 /High	0.10	Very Low (2)
											Procurement	Responsible for material problems in the system failure					
											Finance and Administration	Prepare extra budget for repairment					
								Mitigate	Do mini test when system installed	Reduced probability of system test failure	Engineer	Do the mini test and report result to project manager	0.10	0.10	0.01 /Low	1.00	Top Priority (1)
RTO 2		Acceptance Test Failure	Unaware of Quality Constraints	0.30	0.80	0.24 /High	Threat	Accept	Rework after failure	Extra Cost, late schedule	Project Manager, Project	Define rework schedule	0.30	0.80	0.24 /High	0.25	Low (3)

Risk Identification				Qualitative Analysis				Response Plan					Risk Residual			Response Plan Priority	
Code	Impacted Phase	Risk	Cause	P	I	Risk Rate	Threat/ Opportunity	Possible Risk Response	Response Application Plan	Response Plan Impact	PIC of Response Plan	Expected Actions from PIC	P	I	Risk Residual Rate	Priority Rate	Priority Level
											Engineer, Contractor	and resource plan					
											Engineer	Responsible for system failure					
											Procurement	Responsible for material problems in the system failure					
											Finance and Administration	Prepare extra budget for rework					
								Minor repairment after failure	Late schedule		Engineer	Do repairment	0.50	0.40	0.2 /High	1.00	Top Priority (1)
											Procurement	Responsible for material problems in the system failure					
											Finance and Administration	Prepare extra budget for repairment					
RR01	Reporting and Documentation	Annual Project Report Cost Decrease	Faster Construction Process	0.10	0.05	0.01 /Low	Opportunity	Enhance	Balance upcoming activity duration and resource	Stable schedule	Project Manager, Project Engineer, Contractor	Define new schedule and resource plan	0.50	0.10	0.05 /Low	0.40	Low (3)
											Finance and Administration	Prepare updated budget baseline					
								Exploit	Cancel documentation for one or several periods	Reduced documentation cost	Project Manager, Project Engineer, Architect	Define documentation schedule and resource plan	0.90	0.10	0.09 /Medium	0.50	Medium (2)
											Finance and Administration	Prepare updated budget baseline					
									Use new technology and/ or high	Satisfied stakeholders due to	Project Manager, Project	Define new schedule and	0.70	0.20	0.14 /Medium	1.00	Top Priority

Risk Identification				Qualitative Analysis				Response Plan					Risk Residual			Response Plan Priority	
Code	Impacted Phase	Risk	Cause	P	I	Risk Rate	Threat/ Opportunity	Possible Risk Response	Response Application Plan	Response Plan Impact	PIC of Response Plan	Expected Actions from PIC	P	I	Risk Residual Rate	Priority Rate	Priority Level
									quality resource when available	faster schedule, human resource usage decrease	Engineer, Contractor	resource plan					y (1)
											Procurement	Ensure new technology is available					
											Finance and Administration	Prepare updated budget baseline					
RR02		Annual Project Report Cost Increase	Late Construction Process	0.70	0.05	0.04 /Low	Threat	Avoid	Subcontract work	Stable schedule	Project Manager, Project Engineer, Engineer, Procurement, Contractor	Define subcontract schedule and resource plan	0.10	0.05	0.01 /Low	1.00	Top Priority (1)
											Finance and Administration	Prepare updated budget baseline					
									Cancel documentation for one or several periods	Reduced documentation cost	Project Manager, Project Engineer, Engineer, Architect	Define documentation schedule and resource plan	0.10	0.05	0.01 /Low	1.00	Top Priority (1)
											Finance and Administration	Prepare updated budget baseline					
								Mitigate	Overtime to balance schedule	Extra cost, unsatisfied worker	Project Manager, Project Engineer, Contractor	Define overtime schedule and resource plan	0.50	0.05	0.03 /Low	0.33	Low (3)
											Finance and Administration	Prepare updated budget baseline					
								Transfer	Outsourcing to balance schedule	Extra cost	Project Manager, Project Engineer, Contractor	Define outsourcing schedule and resource plan	0.30	0.20	0.06 /Medium	0.33	Low (4)

Risk Identification				Qualitative Analysis				Response Plan					Risk Residual			Response Plan Priority	
Code	Impacted Phase	Risk	Cause	P	I	Risk Rate	Threat/ Opportunity	Possible Risk Response	Response Application Plan	Response Plan Impact	PIC of Response Plan	Expected Actions from PIC	P	I	Risk Residual Rate	Priority Rate	Priority Level
											Finance and Administration	Prepare updated budget baseline					
								Accept	Accept the late schedule	Late schedule, human resource usage increase	Project Manager, Project Engineer, Contractor	Define late schedule and resource plan	0.90	0.05	0.36 /High	0.01	Very Low (5)
											Finance and Administration	Prepare updated budget baseline					

[Back to Chapter N. Risk Analysis](#)

Appendix G. Schedule Three Point Estimation

WBS	Task Name	Duration		
		Optimistic	Most-Likely	Pessimistic
1	ITF Establishment in Cilincing	296	538	795
1.1	Construction Planning	4	8	11
1.1.1	Business Requirements List	2	6	7
1.1.1.1	System Engineering	2	6	7
1.1.1.2	Site Development	2	6	7
1.1.1.3	Civil Structures	2	6	7
1.1.1.4	Electrical Systems	2	6	7
1.1.1.5	Thermal Systems	2	6	7
1.1.1.6	Storage Systems	2	6	7
1.1.1.7	Mechanical Systems	2	6	7
1.1.1.8	Instrumentation and Control Systems	2	6	7
1.1.1.9	Auxiliary Systems	2	6	7
1.1.1.10	Security System	2	6	7
1.1.1.11	Flow Systems	2	6	7
1.1.1.12	Environmental Systems	2	6	7
1.1.2	Process Models Design	4	8	11
1.1.2.1	System Engineering	4	8	11
1.1.2.2	Site Development	4	8	11
1.1.2.3	Civil Structures	4	8	11
1.1.2.4	Electrical Systems	4	8	11
1.1.2.5	Thermal Systems	4	8	11

WBS	Task Name	Duration		
		Optimistic	Most-Likely	Pessimistic
1.1.2.6	Storage Systems	4	8	11
1.1.2.7	Mechanical Systems	4	8	11
1.1.2.8	Instrumentation and Control Systems	4	8	11
1.1.2.9	Auxiliary Systems	4	8	11
1.1.2.10	Security System	4	8	11
1.1.2.11	Flow Systems	4	8	11
1.1.2.12	Environmental Systems	4	8	11
1.2	Construction	244	432	518
1.2.1	Site Development	45	85	102
1.2.2	Civil Structures	162	272	326
1.2.3	Electrical Systems	4	10	12
1.2.4	Thermal Systems	5	15	18
1.2.5	Storage Systems	3	5	6
1.2.6	Mechanical Systems	10	20	24
1.2.7	Instrumentation and Control Systems	18	30	36
1.2.8	Auxiliary Systems	5	7	8
1.2.9	Security System	5	7	8
1.2.10	Flow Systems	10	20	24
1.2.11	Environmental Systems	15	25	30
1.3	Legal and Regulatory	46	86	159
1.3.1	Licensing	30	59	69
1.3.1.1	Waste Treatment	5	7	9

WBS	Task Name	Duration		
		Optimistic	Most-Likely	Pessimistic
1.3.1.2	Machinery	11	22	25
1.3.1.3	Plumbing	14	30	35
1.3.1.4	Electricity	14	30	35
1.3.1.5	Land and Building	14	30	35
1.3.2	Government Permitting and Agreement	14	30	40
1.3.2.1	Acceptance Criteria	5	14	30
1.3.2.2	Issuance of Permit	1	3	10
1.3.3	Land Acquisition	15	30	60
1.3.3.1	Financing	15	30	60
1.3.4	Sustainability Impact Assessment	13	18	37
1.3.4.1	Preliminary Assessment	5	7	12
1.3.4.2	Impact Review	2	3	5
1.3.4.3	Magnitude Assessment	3	4	10
1.3.4.4	Mitigation Plan	3	4	10
1.3.5	Contractor Agreements	7	18	37
1.3.5.1	Tender Auctions	5	14	25
1.3.5.2	Bargaining	1	3	10
1.3.5.3	Contract Agreement	1	1	2
1.3.6	Work Agreements	4	12	34
1.3.6.1	Initial Agreement	1	2	10
1.3.6.2	Bargaining	2	8	14
1.3.6.3	Final Agreement	1	2	10

WBS	Task Name	Duration		
		Optimistic	Most-Likely	Pessimistic
1.3.7	Other Legal/Regulatory Requirements	5	6	20
1.4	Testing	2	6	100
1.4.1	System Test	1	3	50
1.4.2	Acceptance Test	1	3	50
1.5	Reporting and Documentation	250	452	636
1.5.1	Annual Project Report	Repetitive during construction		
1.5.1.1	Project Documentation			
1.5.1.2	Report Writing			
1.5.1.3	Report Publishing			
1.5.2	Final Project Report	4	14	18
1.5.2.1	Report Writing	3	12	15
1.5.2.2	Report Publishing	1	2	3

[Back to Chapter N. Risk Analysis](#)

Appendix H. Cost Three Point Estimation

Resource Name	Cost		
	Optimistic	Most-likely	Pessimistic
Total	1,291,739,716,400.00	2,151,909,564,000.00	3,353,393,912,400.00
Project Manager	871,486,560.00	1,210,398,000.00	1,267,924,000.00
Project Engineer	871,214,400.00	1,210,020,000.00	1,229,200,000.00
Main Contractor	155,453,760.00	215,908,000.00	227,892,000.00
Sub-Contractor	124,992,000.00	173,600,000.00	183,190,000.00
Finance and Administration	774,406,080.00	1,075,564,000.00	1,087,548,000.00
Surveyor	16,863,840.00	23,422,000.00	30,618,000.00
Procurement	155,453,760.00	215,908,000.00	227,892,000.00
Architect	231,840,000.00	322,000,000.00	331,590,000.00
Engineer	353,304,000.00	490,700,000.00	500,290,000.00
MSW Recycling Package	90,014,794,800.00	150,024,658,000.00	162,879,990,000.00
Extruding Machine	1,203,694,800.00	2,006,158,000.00	2,102,044,000.00
Leftover Waste Dryer	1,203,694,800.00	2,006,158,000.00	2,234,554,000.00
Forklift	1,295,221,200.00	2,158,702,000.00	2,213,666,000.00
Building Material (Site Development)	118,784,400.00	197,974,000.00	203,014,000.00
Building Material (Civil Structures)	370,213,200.00	617,022,000.00	696,136,000.00
Bailing Machine	423,696,000.00	706,160,000.00	725,662,000.00
Wire Machine	507,696,000.00	846,160,000.00	942,914,000.00
Fertilizer Packaging System	193,536,000.00	322,560,000.00	368,788,000.00
Fix Fence	360,502,800.00	600,838,000.00	616,434,000.00

Resource Name	Cost		
	Optimistic	Most-likely	Pessimistic
CCTV	15,304,800.00	25,508,000.00	29,218,000.00
Personal Computer	72,718,800.00	121,198,000.00	138,488,000.00
Security System	14,103,600.00	23,506,000.00	25,102,000.00
Electricity Installment	15,002,400.00	25,004,000.00	26,096,000.00
Generator Set	534,576,000.00	890,960,000.00	955,444,000.00
Communication Package	16,800,000.00	28,000,000.00	32,172,000.00
Conveyor	675,696,000.00	1,126,160,000.00	1,241,506,000.00
Sorting Machine Package	3,914,786,400.00	6,524,644,000.00	7,419,650,000.00
Plumbing System	410,407,200.00	684,012,000.00	713,258,000.00
Smart Thermal System	118,196,400.00	196,994,000.00	202,020,000.00
Land and Land Acquisition	1,186,700,810,400.00	1,977,834,684,000.00	3,164,535,494,400.00
Documentation	2,156,000.00	2,436,000.00	3,024,000.00
Report Writing	868,000.00	938,000.00	1,092,000.00
Report Publishing	1,442,000.00	1,610,000.00	2,002,000.00

[Back to Chapter N. Risk Analysis](#)